



SNUBBER TEST EQUIPMENT

**Barker/ Diacon IPST10 In Place Tester  
In Place Test Machine**

**Standard Capacities/Performance**

**Lower Ram**

Maximum Pressure (activation testing)	12000	psi	810.81	bar
Minimum Flow Rate (Lockup)	10	gpm	37.85	liter/min
Maximum Flow Rate (Bleed)	1	gpm	3.79	liter/min

**Instrumentation Accuracies**

Flow (velocity)	+/- 0.5	% of flowmeter span
Pressure (force)	+/- 0.5	% span

Data Conversion      16 bit

**Power Requirement**                      480V/3ph/20A                      Others available

**Interconnect Hoses/Cables**

Electrical Cables	25	Feet	8	Meters
Main Hydraulic Hoses	50	Feet	15	Meters
Snubber Interconnect Hoses	10	Feet	3	Meters

**Overall Maximum Size/Weight**                      24"W x 40" Lx 42" H

**Weight**    500                      lbs



**IPST10 Snubber Tester**